



SUDAN UNIVERSITY OF SCIENCE & TECHNOLOGY

College Of Graduate Study

**Importance of Applying Quality Control in
Elgadida X-Ray Department of K.T.H**

Prepared By:


Huda Abdella Hamid

*A Thesis Submitted For Partial Fulfillment Of M.Sc .Degree
in Diagnostic Radiologic Technology*

Under Supervision of:

Dr. Ibrahim A. Rahim Shaddad
Ph.D in Nuclear Physics

October 2004



قال تعالى:

صدق الله العظيم

To

My Parents ...

My Sisters and Brothers ...

My Teachers from whom I had benefited

greatly ...

My Friends and Colleagues ...

Huda

CONTENTS

Subjects	Page
Acknowledgement	i
Abbreviations	ii

Abstract (English)	iii
Abstract (Arabic)	iv
List of Tables	v
List of Figures	vi

Chapter One

Introduction	1
1.1. Quality assurance	2
1.2. Research objectives	4
1.3. The reasons of choosing this topic for research	4
1.4. Methodology	4
1.5. Hypothesis	5
1.6. Type of study	5

Chapter Two

Literature Review	6
2.1. Quality assurance (QA)	6
2.1.1. Quality assurances in diagnostic radiology	6
2.1.2. Quality control (QC)	6
2.1.3. Radiographic quality control	7
2.1.3.1 Image quality control	7
2.1.4. Quality assurance programme (QAP)	8
2.1.5. Quality Administrative procedures (QADP)	8
2.1.6. Benefits of quality assurance program	9
2.1.7. Implementing a quality assurance program	9
2.1.8. The departmental QA Committee	10
2.1.9. The framework of a quality assurance program	11
2-2 Quality control program for radiographic units	16
2-2-1 Visual inspection	16

2-2-2 Environmental inspection	18
2-2-3 Performance testing	18
2-2-4 Reject Analyses	18
2-2-5 Radiation safety policies and procedures	22
2-2-5-1 Policy for holding patient	22
2-2-5-2 Policy for presence of individuals in the room during radiation Exposure	23
2-2-5-3 Policy for pregnant patients	24
2-2-5-4 Policy for pregnant Employees	24
2-2-6 Set of QC protocols are used for the x-ray diagnostic machines. Those protocols are including the following	25
2-2-6-1 Total radiographic system check for image quality	25
2-2-6-2 Consistency of radiation output using a digital KV meter	27
2-2-6-3 Consistency of radiation at different MA setting using a digital meter	29
2-2-6-4 Assessment of kilovoltage applied to the x-ray tube using digital meter	30
2-2-6-5 Accuracy of exposure timer using a spinning top	32
2-2-6-6 Accuracy of exposure timer using digital timer meter	33
2-2-6-7 Assessment of focal spot size using focal spot test tool	35
2-2-6-8 Accuracy of collimation of the light beam diaphragm and x-ray beam alignment using the test tool	36
2-2-6-9 Accuracy of collimation when using non adjustable cones and diaphragm	38
2-2-6-10 Assessment half value layer (HVL) using test tool filtration	39

2-2-6-11 Assessment of grid alignment using test tool purpose	40
2-2-6-12 Assessment of the uniformity of a grid using grid movement test two	42
2-2-7 TESTS OF DARK ROOM	44
2-2-7-1 Cassette and screen identification	44
2-2-7-2 Assessment of screen film contact using wire mesh	45
2-2-7-3 Assessment of cassette lightness	46
2-2-7-4 Assessment of relative speed of intensifying screens for replacement	47
2-2-7-5 Processor quality control	49
2-2-7-6 Dark room fog check	56
2-2-7-7 Leakage testing and processing area condition	58
2-2-7-8 Film and chemical storage	59
2-2-7-9 View box Quality Control	59

Chapter Three

Methods & Experiments	62
3.1. The equipment and procedure	62
3.2. Data collection	63

Chapter Four

Results & Discussion	67
4-1. Results	67
4.1.1. Result of research questionnaires and direct interviewing	67
4.1.1.1. First questionnaire (for technologist)	67
4.1.1.2. Questionnaire No. (2) for Administrators and Engineers	68
4.1.1.3. Questionnaire No 3 for the Radiologist.	69
4.1.1.4. From all of three questionnaires	70
4.1.1.5. Implementing of quality control in Elgadida x-ray	70

department	
4.1.1.6. Availability of test tools	71
4.1.1.7. Acceptance test of the machine in the department:	74
4.1.1.8. Training courses for the technologist in the department.	74
4.1.1.9. The present of radiation protection officer	74
4.1.1.10. Result of applying reject analysis in the department	74
4.1.2. Result of reject analysis	79
4.1.3. Testing of x-ray tube	83
4.1.3.1. KVP and time accuracy	83
4.1.3.2. Relative MA & MAS linearity (using the KVP meter)	84
4.1.3.3. MAS Consistency	84
4.1.3.4. KVP, time Reproducibility and linearity tests	85
4.1.3.5. Measurements of HVL of the x-ray unit	86
4.1.3.6. Check of Radiation field Accuracy of collimator and	88
LBD	
4.1.3.7. Focal spot size test	88
4.1.4. Testing of darkroom, cassette, intensifying screen and	89
films	
4.1.4.1. Test of light tightness of the darkroom	89
4.1.4.2. Safe light test	89
4.1.4.3. Testing of intensifying screen	90
4.1.4.4. Testing of cassettes	91
4.1.4.5. Test of films sensitometry	91
4.1.4.6. Test of manual processor	91
4.1.4.7. Test of grid alignment & movement grid	92
4.2 Discussion	93
4.2.1. Effect of implementing of some QA program to the	96

performance in Elgadida X-ray department	
4.2.1.1. Meeting	96
4.2.1.2. Courses	97
4.2.1.3. Reject Analysis	97

Chapter Five

Conclusion & Recommendations	104
5.1. Conclusion	104
5.2. Recommendations	105
References	106

Appendices

Appendix (1) Figures	
Appendix (2) Questionnaire	
Appendix (3) Data file	
